



Case Study Client | Llandid Ltd Role | Principal Contractor

Before: Deck Waterproofing





After: Deck Waterproofing

This six-level multi-storey car park required a complete transformation culminating in a contract value in excess of £1m.

Substantial volumes of concrete repair had to be carried out following years of neglect. The existing asphalt waterproofing to the top deck (2000m²) was beyond economical repair and was replaced as part

Before: Up/down Ramps





After: Up/down Ramps

of our contract using a polymer-modified asphalt including drainage system replacement. Once repaired, the intermediate decks (4000m²) and up/down ramps (300m²) were waterproofed using Sika's car park deck waterproofing system. All soffits, columns and beams were protected with Sikagard anti-carbonation coatings. Cemplas also installed replacement lighting,

Before: Pedestrian Entrances Replaced and Re-Glazed





After: Pedestrian Entrances Replaced and Re-Glazed

a CCTV system, replacement entry and exit barriers and new edge protection throughout. All stairwells were also completely refurbished with all internal doors and pedestrian entrances replaced & re-glazed.

For expert advice, or if you wish to view our previous case studies, please have a look at our website

www.cemplas.co.uk



Cemplas Waterproofing & Concrete Repairs Ltd

Cemplas House, 25A, Breakfield, Ullswater Industrial Estate, Coulsdon CR5 2HS



E: info@cemplas.co.uk W: www.cemplas.co.uk























