



Client | LSG Sky Chefs
Role | Principal Contractor





Client | LSG Sky Chefs Role | Principal Contractor

Before: Aged-Damaged Structure



After: Roof Re-waterproofed

The scope of this refurbishment was to carry out substrate repairs and re-waterproofing to the existing concrete barrel roof measuring some 1,600m².

The existing mineral felt membrane was badly ageddamaged in areas with extensive defects used by vegetation growth. Following removal of the mineral felt the

Before: Outdated & Leaking Roof Lights





After: New 'Barrel' Roof Liights

exposed 20mm cementitious screed was very friable and had to be stabilized prior to being overlayed

Also included in our within the scope of works for our contract was the replacement of the existing outdated and damaged leaking rooflights. For safety reasons a complex crash-deck scaffold had to be created within the building below to enable staff washrooms to continue to be used

Before: Exisiting Damaged Waterproofing





After: Watertight Overlay of Roof

during the rooflight replacement works.

Re-waterproofing to the adjacent roof parking deck was also carried out by Cemplas at the same time.

For further information, or to view our additional case studies, please visit our website www.cemplas.co.uk.



Cemplas Waterproofing & Concrete Repairs Ltd

Cemplas House, 25a, Breakfield, Ullswater Industrial Estate, Coulsdon CR5 2HS



E: info@cemplas.co.uk W: www.cemplas.co.uk























