

Case Study // Car Parks //

Client | Savills UK
Role | Principal Contractor

Office Parking Cygnus House, Fleet

SCOPE

- // Deck Waterproofing
- // Line Marking & Instructions

DETAILS

- // Office car park
- // Fleece reinforcement overbanding to the daywork joints
- // 735m² of waterproof wearing surface (including ramps)



Case Study // Car Parks

Client | Savills UK
Role | Principal Contractor

Before: Poor Quality Environment



After: Overall Surface Enhanced

The scope of this refurbishment was to repair and re-waterproof the existing surface including the split daywork joints, which had been leaking for some time.

Following substrate preparation which included captive blasting and line removal, wheel indents and other defects

Before: Damage to Deck Surface



After: Fully Protected & Watertight Deck

in the existing asphalt surface were repaired incorporating Tremco's CP581 fleece reinforcement overbanding being used also to treat daywork joint splits.

Following minor drainage repairs and alterations, the top deck of the car park was fully re-waterproofed using Tremco's Rapid Cure MMA Deck Waterproofing System.

Before: Faded Line Marking & Instructions



After: Line Marking & Instructions Reinstated

All works had to be completed over a long weekend to minimise disruption to the car park's business users during the working week.

For further advice and/or information regarding ALL of our services, please visit www.cemplas.co.uk or contact us via the details below.

Est. 1969
cemplas //
REPAIR || PROTECT || TRANSFORM

Cemplas Waterproofing & Concrete Repairs Ltd
Cemplas House, 25A, Breakfield, Ullswater Estate, Coulsdon, CR5 2HS
T: 020 8654 3149 F: 020 8656 6984
E: info@cemplas.co.uk W: www.cemplas.co.uk



www.cemplas.co.uk