

Case Study Podium Waterproofing



Case Study // Podium Waterproofing

Before: Podium Deck With Water Ingress Into Train Platform Below

Before: Movement Joints Leaking Into Car Park Below







During: New & Bespoke Movement Joints

Tremco's CPG Pumacrete podium deck membrane. bespoke movement joints and a new drainage matting layer. As well as overhauling all of the cast iron drainage system and installation of new drainage channels for surface water run-off.

A new substrate using varying materials including insulation and screed back fill to ensure weight loads were maintained and were installed to bring the build up back to existing levels followed by reinstatement of paviours.



During: Temporary Ramps & Walkways





After: Watertight & Drainage Issues Resolved

The project was logically challenging and required precise planning as all areas affected were directly in front of retail, train station, residential and car park ingress and egress routes needing access some of which 24 hours a day. We constructed temporary ramps and walkways in a phased manor maintaining access to all 3 residential blocks, in excess of 20 retails units and a busy tube/train station. All while the European Cup was on!

For further advice and/or information regarding ALL of our services, please visit www.cemplas.co.uk



During: Podium Deck Waterproofing Membrane

The Wembley Central Shopping Centre is situated above an underground MSCP and Wembley Central Train Station with ongoing water ingress into both the sites below, meant significate waterproofing & associated works were necessary.

The existing paviours and sub-base were excavated to expose the reinforced concrete podium deck slab and undertook detailed drainage surveys. The extensive waterproofing works involved the installation of 1,500m²



Cemplas Waterproofing & Concrete Repairs Ltd

Cemplas House, 25A, Breakfield, Ullswater Industrial Estate, Coulsdon CR5 2HS T: 020 8654 3149 E: info@cemplas.co.uk W: www.cemplas.co.uk